


- ADDITIONAL ON RERQUEST:**
- SAFETY NET
 - LIFTING SLING
 - IN HOUSE TEST CERTIFICATE
 - 3RD PART TEST CERTIFICATE
 - REMOVABLE RIGID HANDRAILS
- GANGWAY DESIGNED TO ISO 7061**
- TYPE APPROVAL TEST RATED TO (5 kN/m²) = 1835 kg
 SWL LOAD (4 kN/m²) = 1470 kg
 No PERSONS (SWL / 75) = 19 PERSONS
- ANGLE OF USE: MIN 0° TO MAX 50°

THIS DESIGN OR DRAWING IS THE PROPERTY OF TYNE GANGWAY STRUCTURES AND RENEGADA GROUP - WALKER SITE, WINDMILLER ROAD, WALKER, NEWCASTLE UPON TYNE, NE10 0JH. WHICH IS CONFIDENTIAL AND MUST NOT BE GIVEN, LOANED, COPIED, OR OTHERWISE REVEALED TO A THIRD PARTY WITHOUT WRITTEN CONSENT OF THE COMPANY. COPYRIGHT RESERVED.				GENERAL TOLERANCES MACHINING ± 0.5 ANGULAR ± 0.5° FABRICATION UP TO 300 ± 1 301 TO 1000 ± 2 1001 AND ABOVE ± 3		MANUFACTURING SPECIFICATIONS WELD PROCEDURES STEEL: EN ISO 15614-1 ALUMINIUM: EN ISO 15614-2 FIRST ANGLE PROJECTION		GENERAL NOTES 1. WELDING SYMBOLS STANDARD TO ISO 2553 METHOD A 2. REMOVE ALL BURRS AND SHARP EDGES 3. ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE STATED		MATERIAL EST WEIGHT N/A  TEL: (0191) 261 3627 E-MAIL: TYNES@TYNEGANGWAY.CO.UK		SEE BOM SHEET 1 OF 1 SCALE DNS JOB No CUSTOMER		DWG No: TG-00004116-GA DESCRIPTION: 6m STANDARD SALA C/W HOOKS, QUAY ROLLER, ROPES & STANCHIONS	
REVISION HISTORY															
A	ORIGINAL ISSUE	16/08/21	JD	SQ											
REV	DESCRIPTION	DATE	DRAWN	CHECKED											